

Name:
Street
City:
State:
Zip:
Phone:
Email:

# **SCOPE OF WORK:**

# **JAMES HARDIE RESIDE**

#### **REPLACE CHIMNEY SIDING AS FOLLOWS**

- All existing chimney siding is to be removed and placed in a dumpster; hauled away upon completion.
- Supply and Install James Hardie siding to areas to be resided per Hardie specifications-following style

Siding: Primed Siding: Primed CHIMNEY SIDING

OSB sheathing installation if necessary, to be charged at a rate of \$75.00/4x8 sheet

- Bed molding will be removed; replaced with new PVC bedmolding
- Flashing to be installed over all brick-ledges; and terminations.
- Install slip sheet flashing behin all Hardie butt joints, per Hardie specifications
- Note: does not caulk butt joints, per Hardie specifications
- Install small starter strip on bottom-row for proper angle of siding.
- Install a house wrap moisture barrier to help stop wind, rain and moisture from entering house
- Remove inside corner boards; Install Hardietrim® planks on inside corner boards
- Remove outside corner boards and install Hardie trimplanks on outside corners-double 5/4 x 4
- Rehang light fixtures & downspouts and any other items that were removed for siding including pinning down cables & wires.

#### Replace additional items:

- Replace all underlayment sheathing and replace with OSB sheathing
- Replace panels beneath overhang wall sections/chimneys with solid Hardie panels

#### **Subtotal for Siding Replacement:**

\$ 3,567.00

NOTE:If unforseen damage due to wood rot, insect infestation, water damage, etc. is uncovered, the following additional charges would apply:

4' X 8' OSB Plywood:	\$75.00/sheet
2 x 4 or 2 x 6	\$6.00/ln.ft.
2 x 8 or 2 x 10	\$8.00/ln.ft.

# **PAINTING:**

#### **EXTERIOR CARE AND PREPARATION**

• Pressure wash AS NEEDED to clean any chalking, existing residue and dirt.

Use bleach solution

- Caulk the following, where needed: Trim and Siding
- PREMIUM Sherwin Williams or Porter caulk that has high elasticity to minimize future cracking
- Wire brush and spot prime any rust with oil based primer.
- Customer is responsible to cut back bushes/ shrubs/ trees from surfaces to be painted, where needed.
- With approval from homeowner, ladders may be stacked neatly on the premises for the duration of the project.
- will exercise care around vegetation and plant growth and will attempt to protect them as best possible, however, we cannot guarantee nor do we accept responsibility for any damages.
- The following surfaces ARE NOT included in this proposal: Brick Façade, Decking, Fencing, Concrete surfaces, other siding unless listed below:

### PAINT SPECIFICATIONS:

## **Sherwin Williams**

## **Duration**

• Chimney Siding 2 coats Exterior 100% Acrylic Finish: Satin

Same color/sheen as current;

Chimney (2) coats 1 coat ProCryl® or BondPlex® Metal Primer

Cap minimum 1 coat Exterior 100% Acrylic Finish

Subtotal for Painting: \$ 1,303.00

AVAILABLE DISCOUNTED PRICE WHEN CLIENT IS

CHOICE 2

AVAILABLE DISCOUNTED PRICE WHEN CLIENT IS PAYING WITH OWN FUNDS:

\$

4,578.00

#### TERMS AND CONDITIONS

We hereby propose to furnish labor and materials – complete in accordance with the above specifications.

Deposits Required: (not applicable when financing option is selected)

• 1/3 of the total due near time of signing, 1/3 due upon completion of construction, final 1/3 is due upon completion of job.

**PAYMENT TERMS:** 

Payment is due by check at intervals or financing terms shown above:

NOTE: PAYMENT BY CREDIT CARD RESULTS IN A 2.5% FEE

NOTE: Due to economic conditions, material availability and pricing is unstable. Therefore, the pricing stated above is only valid for 30 days from the proposal date.

Date: 11/20/2024

ACCEPTANCE OF CONTRACT TERMS:

The above prices, specifications and conditions are hereb acce ted. B signing below you acknowledge and accept the above prices, specifications, terms and conditions and authorize to the work as specified.

DATE: SIGNATURE:

Electronic signature file available upon request

OR: To schedule a project date, please send back signed proposal:

All work is to be completed in a workmanlike manner according to standard practices. Any alterations or deviation from

above specifications will become an extra charge over and above the estimate.